

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-30509-00-00
Spot: S2NWNESE Sec/Twnshp/Rge: 9-20S-12W
2300 feet from S Section Line, 990 feet from E Section Line
Lease Name: HULME C Well #: 8
County: BARTON Total Vertical Depth: 3421 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3415		100 SX
SURF	8.625	175		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2013 11:00 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELLL SERVICE, INC.
Proposal Rcvd. from: ROCH MILLER Company: EDISON OPERATING Phone: (620) 786-5161

Proposed
Plugging
Method:

Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 15 sx gel.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/25/2013 4:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1300', 670' and 160'.
Ran tubing to 3240' and pumped 15 sx gel followed by 50 sx cement w/100# hulls.
Pulled tubing to 1300' and pumped 50 sx cement w/100 # hulls.
Pulled tubing to 680'. Circulated cement to surface with 125 sx cement and 200 # hulls on casing and surface pipe.
Pulled tubing. Topped off with 5 sx cement.

GPS: 38.32525 -098.64905

Perfs:

Top	Bot	Thru	Comments
3415	3421		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: ALLIED CEMENTING TICKET # 61776

Plugged through: CSG 3 1/2

AUG 02 2013

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Bruce Rodie
8/14/13 (TECHNICIAN)

CM

JUL 30 2013