

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04924-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 21-20S-12W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: PHILLIPS Well #: 4
County: BARTON Total Vertical Depth: 3495 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3495		100 SX
SURF	8.625	250		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/24/2013 12:30 PM

Plug Co. License No.: 6123 Plug Co. Name: CHASE WELLL SERVICE, INC.

Proposal Rcvd. from: BRIAN MCCOY Company: EDISON OPERATING CO. LLC Phone: (316) 214-3658

Proposed	Ordered 400 sx 60/40 pozmix 4% gel cement, 15 sx gel and 450 # hulls.
Plugging	08/05/2013- Ordered 100 sx 60/40 pozmix 4% gel cement.
Method:	Perforations: 1300', 630' and 225'.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 08/05/2013 10:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3400' and pumped 15 sx gel followed by 50 sx cement.
 Pulled tubing to 1285' and pumped 60 sx cement w/100 # hulls.
 Pulled tubing to 640' and pumped 290 sx cement.
 Had colored water circulating on both sides but no good cement circulated.
 Shut in and down for the night.
 08/05/2013- Hooked up to casing and pumped 75 sx cement. Cement circulated to surface.
 GPS: 38.29285 -098.65379

Perfs:

Top	Bot	Thru	Comments
3445	3450		

Remarks: ALLIED CEMENTING TICKET # 64074

Plugged through: TBG

District: 04

Signed Ray Dinkeld
8/14/13

(TECHNICIAN) CM
RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

AUG 05 2013

AUG 09 2013

CONSERVATION DIVISION
WICHITA, KS