

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23620-00-00
Spot: N2SESENW Sec/Twnshp/Rge: 21-27S-4E
3043 feet from S Section Line, 2955 feet from E Section Line
Lease Name: WEST LOOMIS Well #: 1A
County: BUTLER Total Vertical Depth: 2362 feet

Operator License No.: 32693
Op Name: HAWKINS OIL, LLC
Address: 427 S BOSTON AVE STE 915
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2340		115 SX
SURF	8.625	218		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/16/2013 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: WAYNE BAKER Company: HAWKINS OIL LLC Phone: (918) 504-8059

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/16/2013 1:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 2282, CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS CLASS A COMMON 3% CC DISPLACED IN CASING. RAN WIRE LINE, DID NOT TAG CEMENT RIH W/TUBING @ 2282 ESTABLISHED CIRCULATION, CONSOLIDATED MIXED & PUMPED 35 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT @2220. RIH W/TUBING @ 1941, CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT @ 1770. PRESSURED CASING, HELD OK. RIH ON WIRELINE SHOT SQUEEZE HOLES 270-271 (4 HOLES). SWEDGED INTO 5 1/2" CSG, ESTABLISHED CIRCULATION, CONSLIDATED MIXED & PUMPED 110 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #41644.

Perfs:

Top	Bot	Thru	Comments
2340	2360	OH	
1960	1970	OH	

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: CONSOLIDATED TICKET #41644

Plugged through: TBG

AUG 13 2013

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

Duane Krueger
8/14/13 (TECHNICIAN)