

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26488-00-00
Spot: S2SENE Sec/Twnshp/Rge: 19-15S-20W
1045 feet from N Section Line, 330 feet from E Section Line
Lease Name: ROGERS B Well #: 1
County: ELLIS Total Vertical Depth: 4050 feet

Operator License No.: 6484
Op Name: ANDERSON ENERGY, INC.
Address: 300 W DOUGLAS AVE, STE 410
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4044	1618	180 sx
SURF	8.625	304		200 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/07/2013 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: PRESTON DREILING Company: ANDERSON ENERGY INC. Phone: (316) 263-1006

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.
CIBP at 3850' covered with 5 sx cement.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/07/2013 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Perf Tech shot pipe at 1618'. Pulled casing to 1475'. Allied rigged to casing and pumped 75 sx cement w/300 # hulls.
Pulled casing to 625' and pumped 100 sx cement w/300 # hulls mixed in.
Pulled casing to 350' and pumped 40 sx cement w/100 # hulls mixed in.
Pulled casing to 150' and pumped 30 sx cement to circulate cement to surface.
Pulled casing. Topped off 8 5/8" casing with 20 sx cement. Hole standing full.
GPS: 38.73703 -099.58018

Remarks: ALLIED CEMENTING TICKET # 60211

Plugged through: CSG


KCC WICHITA

AUG 15 2013

RECEIVED

District: 04

Signed


8/16/13 (TECHNICIAN)

CM

AUG 08 2013