

To: 2 040390
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-2-88
API NUMBER 15- 077-20,287-0000
C NE NW, SEC. 18, T 32 S, R 9 WXX

TECHNICIAN'S PLUGGING REPORT

316
669-8219

Operator License # 9524
Operator: Gypsy Drilling Company - Tom Weems
Name & Address 3730 N. Halstead Box 2558
Hutchinson, KS 67501 67504-2558
Lease Name Werner Well # 3
County Harper 141.38
Well Total Depth 4350 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clark Corporation License Number 5105
Address Medicine Lodge, Kansas

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Elmo Morganstein
(company name) Clark Corporation (phone) _____

were: PBTD @4330 4 1/2" @4341 Sand back to 4300' and dump 5 sxs, 3 sxs hulls,
10 sxs gel, 110 sxs 60/40 pozmix

Plugging Proposal Received by District #2 Office
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____
Operations Completed: Hour: 13:15 Day: 26 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT The 4 1/2" casing was sanded back to 4300' and capped with 5 sxs cement
through the dump bailer. The 4 1/2" casing was shot off and recovered from 3350'.
The top was squeeze plugged through the 8 5/8" surface casing by pumping 300#
pf hulls, 10 sxs gel and 110 sxs 60/40 pozmix.

Remarks: B. J. Titan 600 MX 250 SI
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-7-88 WK

INV. NO. 20031 2-26

MAR 7 1988
3-7-88
CONSERVATION DIVISION
Wichita, Kansas

Signed [Signature]
(TECHNICIAN)