

2 040391

2-26-88

230

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19- 077-20,287-0000

C=^{NW}SE NE, SEC. 18, T 32 S, R 9 W/X

3300 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9524

Lease Name Werner Well # 1

Operator: Gypsy Drilling Company

County Harper 140.73

Name: Tom Weems

Address: 3730 N. Holstead Box 2558

Well Total Depth 4330 feet

Hutchinson, KS 67504-2558

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 206

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clark Corporation License Number _____

Address Medicine Lodge, Kansas

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Elmo Morganstein

(company name) Clark Corporation (phone) _____

were: PBD @4309 5 1/2" @4329 Perf @4300-4325

Sand to 4250' and dump 5 sxs. Pump 3 hulls, 10 gel, 110 60/40 pozmix

Plugging Proposal Received by District #2 Office
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 10:30 Day: 26 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT Sand was dumped down the 5 1/2" casing to 4250' and capped with 5 sxs cement through the dump bailer. The 4 1/2" casing was shot off and recovered from 3430'. The top was squeeze plugged through the 8 5/8" surface casing by pumping 300# hulls, 10 sxs gel and 110 sxs 60/40 poz

Remarks: B.J.Titan MX 800# SI 600#
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed _____
(TECHNICIAN)

DATE 3-7-88 MAR 7 1988

CONV. NO. 20030 CONSERVATION DIVISION 3-7-88
2-26