

15735-20637-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT  
STATE CORPORATION COMMISSION  
RECEIVED  
JUN 28 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Alpine Drilling Company  
Complete Address 800 Bitting Bldg., Wichita, Kansas  
Lease Name Gish "B" Well No. 1  
Location C NW SE Sec. 23 Twp. 18 Rge. (E) (W) 21  
County Ness Total Depth 4180'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Gabbert - Jones Drlg.  
Address Wichita, Kansas License No.         
Operation Completed: Hour 1:45 P Day 27 Month 6 Year 1972

The above well was plugged as follows:

RTD 4180' 8 5/8 csg set at 327' cwc Cmt Mat. 50-50 poz cmt W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 50 sk  
cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 25 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 6/29/72  
INV. NO. 5954-W

Signed: Red J. Massey  
Well Plugging Supervisor