

15-007-30390-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 27 1972
12-27-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Walters Drlg. Co.

Complete Address 400 Insurance Bldg Wichita, KS

Lease Name Swayden Well No. 2

Location C SE/SW Sec. 14 Twp. 32 Rge. 15 (E) (W) W

County Barber Total Depth 5030

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co. Inc

Address Box 1182 Great Bend, KS License No. 623

Operation Completed: Hour 11:00 AM Day 23 Month 12 Year 1972

The above well was plugged as follows:

275 ft 8 5/8 surface pipe cemented with 200 sacks. 5026 ft 5 1/2 long
string cemented with 150 sacks. Top perf. 4960 ft. Sand to 4300 ft.
5 sacks cement with bailer. Pulled 3800 ft 5 1/2. Set 10 ft rock
bridge at 360 ft. Fill hole with 6 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 12/27/72

INV. NO. 6785-W