

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED

AUG 21 1972
8-21-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Ferguson Oil Co. Inc.

Complete Address 2700 Liberty Tower 100 Broadway Oklahoma City, OK

Lease Name Larkin Well No. 2

Location C SW/SE Sec. 14 Twp. 32 Rge. 15 (E) (W) W

County Barber Total Depth 5013

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1182 Great Bend, Ks License No. 623

Operation Completed: Hour 10:00 AM Day 19 Month 8 Year 1972

The above well was plugged as follows:

272 ft 8 5/8 surface pipe cement circulated. 5000 ft 5 1/2 long string
cemented with 140 sacks. Top perf. 4941 ft. Plug set at 4591 ft.
Sand to 4525 ft., 10 sacks cement with bailer. Pulled 4000 ft 5 1/2.
Set 10 ft rock bridge at 250 ft. Fill hole with 4 yds redimix.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 8/21/72

INV. NO. 6194-W