

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
3-17-72  
MAR 17 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Aylward Drlg. Co.

Complete Address 909 1st Natl Bldg. Wichita, Ks

Lease Name Skinner Z Well No. 1

Location SW/NE Sec. 14 Twp. 32 Rge. 15 (E) (W) W

County Barber Total Depth 5070

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 2:00 PM Day 16 Month 3 Year 1972

The above well was plugged as follows:

272 ft 8 5/8 surface pipe cement circulated. 5069 ft 5 1/2 long string  
cemented with 150 sacks. Top perf. 4992 ft. Sand back to 4980 ft,  
5 sacks cement with bailer. Pulled 3700 ft 5 1/2. Set 10 ft rock bridge  
at 250 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: J. Russell Biberstein  
Well Plugging Supervisor

INVOICED

DATE 3-17-72

INV. NO. 5362-11