

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 1 1963
5-1-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Co.

Complete Address: 1020 North Main, Hutchinson, Kansas

Lease Name Lonker Well No. # 5

Location C N/2 N/2 NW Sec. 1 Twp. 33 Rge. 13 (E) W (W) W

County Barber Total Depth 4585

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Leben Drilling Co.

Address: 905 Central Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 8:30PM Day 29th Month April Year 1963

The Above well was plugged as follows:

475' of 8 5/8" surface pipe, cement circulated with 275 sacks.

Hole was filled with mud to 240', 1st cementing plug, 1/4 sack hulls,

cemented with 20 sacks. Hole was filled to 40', 2nd cementing plug,

1/4 sack hulls, cemented with 10 sacks to base cellar. Rat hole bridged

and cemented with 5 sacks.

Bottom formation was cemented off with 40 sacks, from 4565' to 4437'.

Cementing was done by Halliburton Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/1/63
INV. NO. 6989-4

Signed: Archie Elving
Well Plugging Supervisor