

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1965
2-26-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212. North Market
Wichita 2, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name G. S. Lonker Well No. # 2

Location C NE NW Sec. 1 Twp. 33 Rge. 13 (E) (W)

County Barber Total Depth 3845'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 3:00PM Day 25th Month Feb. Year 1965

The Above well was plugged as follows:

545' of 8 5/8" surface pipe, cemented with 300 sacks. 3832' of 5 1/2" long
string, cemented with 200 sacks. Open hole. Bottom of the hole was sand-
ed to 3820, and cemented with 5 sacks. 2565' of 5 1/2" long string was re-
covered from the hole. Fluid in the hole was bailed down to 275'. Bridge
plug was set on fluid at 275', and 10' of rock bridge, and cemented with
25 sacks. Hole was filled with mud to 40', and 10' of rock bridge, and
cemented with 10 sacks to the base of the cellar.

INVOLCED

I hereby certify that the above well was plugged as herein stated.

DATE 2/26/65
INV. NO. 736-W

Signed: Archie Elving
Well Plugging Supervisor