

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued May 17, 1967.

Operator's Full Name Skelly Oil Company

Complete Address P. O. Box 649, McCook, Nebraska, 69001

Lease Name G. S. Lonker Well No. # 1

Location C SE NE Sec. 1 Twp. 33 Rge. 13 (E) (W) W

County Barber Total Depth 4003'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company

Address Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 3:30 P.M. Day 15th Month July Year 1967

The above well was plugged as follows:

566' of 8 5/8" surface pipe, cemented with 300 sacks. 3972' of 5 1/2" long
string, cemented with 125 sacks. This is an open hole. Bottom of the hole
was sanded to 3950', and cemented with 20 sacks, through the dump bailer.
2989' of 5 1/2" long String was recovered from the hole. Fluid level in the
hole was at 325', 1st cement plug bridged at 325', rock bridge from 325' to
315', and cemented with 25 sacks from 315' to 240', Hole was filled with
mud to 55', rock bridge from 55' to 45', and cemented with 15 sacks to the
base of the cellar.

RECEIVED

I hereby certify that the above well was plugged as herein stated.

INVOICED

JUL 17 1967

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/17/67

7-17-67
CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 5981-W