

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1964

4-22-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Aylward Drilling Company

Complete Address: 813 1st National Bank Bldg., Wichita, Kansas

Lease Name Skinner "W" Well No. # 2

Location N/2 NE NW Sec. 10 Twp. 32 Rge. 15 (E) (W) W

County Barber Total Depth 4895

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Co.

Address: Box 980, El Dorado, Kansas License No. 547

Operation Completed: Hour 2:00PM Day 20th Month April Year 1964

The Above well was plugged as follows:

310' of 8 5/8" surface pipe, cemented with 270 sacks. 4895' of 5 1/2" long
string, cemented with 75 sacks. Top perferation 4878'. Bottom of the
hole was sanded to 4860', and cemented with 5 sacks. Hole was filled
with mud to 250', with 10' of rock, and cemented with 25 sacks. Hole
was filled with mud to 40', 10' rock bridge, and cemented with 10
sacks to base cellar.
string
3850' of 5 1/2" long, was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/23/64
INV. NO. 9008-W

Signed: Archie Elving
Well Plugging Supervisor