

15-135-21043-0000



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1975
5-27-75
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thunderbird Drilling, Inc.
Complete Address Box 18407, Wichita, Kansas 67218
Lease Name Ryerse "D" Well No. 1
Location SE SW NW Sec. 25 Twp. 18 Rge. (E) (W) 21
County Ness Total Depth 4180'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 1:45 P Day 15 Month 5 Year 1975

The above well was plugged as follows:

RTD 4180' 8 5/8 csg set 300' cwc 175 sx. Flg. Mat. 50-50 poz 2% total gel.
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.
Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set
solid bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 5/29/75
INV. NO. 1401-W

Signed: Ken Manary
Well Plugging Supervisor