

1 060314

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,895-0000

SE NE SE, SEC. 33, T 32 S, R 11 W/EX
N SE Corner of
1650 feet from ~~XXX~~ section line
W SE Corner of
330 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5038
Operator: Robinson Oil Company
Name & Address: 737 R.H. Garvey Building
Wichita, KS 67202

Lease Name Williams "A" Well # 1
County Barber
Well Total Depth 3800 123.50 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Sweetman Drilling, Inc. License Number 5658

Address 500 Heritage Park Place, Wichita, KS 67202

Company to plug at: Hour: 6:00 am Day: 22 Month: August Year: 19 84

Plugging proposal received from Floyd Hildreth
(company name) Sweetman (phone) 316-278-2676

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 600' with 50 sx cement

2nd plug at 320' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luttie (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:00 am Day: 22 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 600' with 50 sx cement, 2nd plug at 320' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun
(if additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1984
8-24-84
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(City and State) observe this plugging.

Signed Paul A. Luttie (TECHNICIAN)

DATE 8-29-84

INV. NO. 3459 8-22