

7-17-88

1 020164

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-22,196-0000
SE SE NW, SEC. 33, T 32 S, R 11 W&X

TECHNICIAN'S PLUGGING REPORT

2970 feet from S section line
2970 feet from E section line

Operator License # 5255

Lease Name Pelzl-Hall-Wilson Well # 1

Operator: McGinness Oil Company

County Barber 122.04

Name & Address 1026 Union Center Building

Well Total Depth 3755 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 276

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 10:30 a.m. Day: 17 Month: 7 Year: 19 88

Plugging proposal received from Jerb Ogle

(company name) Red Tiger Drilling Company (phone) 316-263-1201

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at Base Anhydrite with 50 sx cement,

2nd plug at 300' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:30 p.m. Day: 17 Month: 7 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 670' with 50 sx cement,

2nd plug at 300' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1988
7-19-88

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 7-26-88

Signed Glenn R. Barlow
(TECHNICIAN)

INV. NO. 21663

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. July 5, 1988

API Number 15-007-22,196-0000

OPERATOR: License # 5255
Name McGinness Oil Company
Address 1026 Union Center Building
City/State/Zip Wichita, Kansas 67202
Contact Person Doug McGinness
Phone (316) 267-6065

SE SE NW Sec. 33 Twp. 32 S. Rg. 11
2970 Ft. from South Line of Section
2970 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5302
Name Red Tiger Drilling Company
City/State Wichita, Kansas

Nearest lease or unit boundary line 330 feet
County Barber

Well Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
X Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

Lease Name Pelzl-Hall-Wilson Well # 1
Ground surface elevation 1478 feet MSL

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Depth to bottom of fresh water 150'
Depth to bottom of usable water 200'

Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 240' +

Conductor pipe required None
Projected Total Depth 3800 feet

Formation Lansing-Kansas City

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 06-22-88 Signature of Operator or Agent Title President

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt
This Authorization Expires 12-23-88 Approved By 7-24-88

EFFECTIVE DATE: 6-28-88

Spud 7-9-88

NO W/W

8 5/8" - 276'
D.6. 340'

SE SE NW Sec. 33 Twp. 32 S. Rg. 11

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep. 650' to 700' or formation with 50 feet of 60-40 F&Z
2nd plug @ ft. deep. 240' + or formation with 40 feet of 60-40 F&Z
3rd plug @ ft. deep. 40' or formation with 10 feet of 60-40 F&Z
4th plug @ ft. deep or formation with feet of
5th plug @ ft. deep or formation with feet of
(2) Rathole to surface minus 5 feet
(b) Mousehole to surface minus 5 feet

PUSHER Terry Jim Rockhold

TD 3755 FORMATION
SURFACE PIPE 8 5/8" @ 276

ANHYDRITE ? ELEVATION
STARTING TIME & DATE 10:30: 7-17-88

COMPLETION TIME & DATE 12:30am 7-17-88
1st PLUG @ 670 FT. W/ 50 SX

2nd PLUG @ 300 FT. W/ 40 SX

3rd PLUG @ 40 FT. W/ 10 SX

4th PLUG @ FT. W/ SX

RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX

WATER WELL PLUGGED W/ X No SX

CEMENT COMPANY BJ Titin

TECHNICIAN Glen Barls

RECEIVED STATE CORPORATION COMMISSION

JUL 19 1988 7-19-88

CONSERVATION DIVISION Wichita, Kansas