

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20852-00-01
Spot: NWNENE Sec/Twnshp/Rge: 9-32S-9W
330 feet from N Section Line, 990 feet from E Section Line
Lease/Unit Name: JACOBSEN Well Number: 2
County: HARPER Total Vertical Depth: 4414 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N. MARKET, STE 1130
WICHITA, KS 67202

Conductor Pipe: Size feet: \$ 143.46
Surface Casing: Size 8.625 feet: 356 250 sx
Production: Size 4.5 feet: 4413 225 sx
Liner: Size feet:

Well Type: SWD UIC Docket No: D21899.0 Date/Time to Plug: 09/03/2002 3:00 PM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: DALE MAY Company: EDMISTON OIL CO INC Phone: (620) 792-6924

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/03/2002 3:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP was set at 3561' and capped 2sxs cement. The casing was recovered from 2572' and pulled to 1350' where 35sxs of cement was spotted. Pulled casing to 850' and spotted 35sxs cement. Pulled to 406' and circulated to surface. Pulled casing and topped off cement.

RECEIVED
KCC DISTRICT #2


SEP 16 2002
9-16-02
WICHITA, KS

Remarks: ALLIED CEMENT. 60/40 POZ. 4% GEL

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 9-18-02

INV. NO. 2003060524