

1 080379

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,598-007-00 *R*
NE NE NW, SEC. 17, T 32 S, R 13 *WEX*
4950 feet from S section line
2940 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Tedrow Well # 1

Operator: TXO Production Corp.
Name & Address: 200 W. Douglas, Suite 300
Wichita, KS 67202

County Barber 163.02

Well Total Depth 5016 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 409

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Oilfield Services License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:25 pm Day: 10 Month: May Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 4316.09 PBD 4316' Perfs at 4209-13'

1st plug sand back to 4016' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 125 sx cement.

Plugging Proposal Received by *J. H. Med* (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:10 pm Day: 10 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4016' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 400 psi and shut in pressure 100 psi

MAY 28 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by BJ-Titan. Recovered 2985 CONSERVATION DIVISION
(If additional description is necessary, use BACK of this Form.)

INVOICED
DATE 6-6-85
NV. NO. 8398

Signed *J. H. Med* (TECHNICIAN)