

1 040193

11-21

15-007-22082-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 9/24/85

C NE NW, SEC. 16, T 32 S, R 13 W/E

4620 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Lease Name Palmer Well # 1

Operator: Patton Oil Company

County Barber 150.31

Name & Address 672 West 4th

Well Total Depth 4625 feet

Hoisington, KS 67544

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 370

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor: Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:45 p.m. Day: 21 Month: 11 Year: 19 88

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4624' PBDT 4600' Perfs at 4504-10, 4490-96'

1st plug sand back to 4440' and dump 5 sx cement on top of sand thorough bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 10 3/4"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 21 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4440' and dumped 5 sx cement on top of
sand through bailer,

2nd plug pumped down 10 3/4" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, released 10 3/4" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3615' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

(I did / did not) observe this plugging.

INVOICED

DEC 1 1988

DATE _____

Signed Stephen J. Pfeiffer
(TECHNICIAN)

INV. NO. 22211