

To: 1 052065
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202
TECHNICIAN'S PLUGGING REPORT

API NUMBER 15- 135-23,739-0000
NW NE, SEC. 33, T 18 S, R 21 W/X
4620 feet from S section line
1980 feet from E section line

Operator License # 6039
Operator: L.D. Drilling, Inc.
Name:
Address: RR 1, Box 183-B
Great Bend, KS 67530

Lease Name Thomas Well # 1
County Ness 136.43
Well Total Depth 4198 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 342

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____
Address _____

Company to plug at: Hour: 10 a.m. Day: 5 Month: 9 Year: 19 96

Plugging proposal received from Mike Kasselmann
(company name) L.D. Drilling, Inc. (phone) 316-793-3051

Core: 5 1/2" at 4193' w/150 sx cement, Perfs at 4192-95, 4147-44, 4156-62', DV at 1357' w/415 sx cement
1st plug pump 200 lbs. hulls, 25 sx cement, gel to 1370', cement to surface.
Check backside.

Plugging Proposal Received by Bill Johnson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 5 Month: 9 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls, 25 sx cement, 24 sx gel, and 45 sx cement. Maximum pressure 2500 psi and shut in 1800 psi.

2nd plug pumped 5 sx cement down 8 5/8" X 5 1/2". Maximum pressure 500 psi and shut in 500 psi.

RECEIVED
STATE CORPORATION COMMISSION
9-9-96
SEP 09 1996

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOLVED

DATE SEP 23 1996
INV. NO. 46534

Signed Richard W. Lucy
(TECHNICIAN)