

1 070217

165

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,281-0000

W/2 W/2 NW, SEC. 33, T 18 S, R 21 W/E
3960 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5266

Lease Name Schniepp Well # 1

Operator: K & E Drilling, Inc.
Name & Address: 100 S. Main, Suite 300
Wichita, KS 67202

County Ness 137.12

Well Total Depth 4219 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 363

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor K & E Drilling, Inc. License Number 5266

Address 100 S. Main, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 10:30 a.m. Day: 27 Month: 8 Year: 1986

Plugging proposal received from Al Hammersmith

(company name) K & E Drilling (phone) 316-792-2729

were: 5 1/2" at 4211' DV'd at 1339' cement circulated Elevation 2115' GL
to surface with 450 sx cement

1st plug pumped 475 sx cement, filled 5 1/2" casing from TD to 0'

Plugging Proposal Received by 2107 Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00 p.m. Day: 27 Month: 8 Year: 1986

ACTUAL PLUGGING REPORT 1st plug pumped 475 sx cement, filled 5 1/2" casing from TD to 0'

Maximum pressure: 2000 psi and shut in 1800 psi

Remarks: Used 60/40 Pozmix 2% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 9-3-86

Signed Dan Goodrow
(TECHNICIAN) SEP 3 1986 9-3-86

INV. NO. 14870 SEP 29 1986 8-27