

5-29-87

1 070360

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,044-0000

SW SW NE, SEC. 36, T 18 S, R 21 W/E

2970 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5088

Lease Name Ryerse Well # "A" 1

Operator: John J. Darrah, Jr.

County Ness 136.70

Name & Address 412 East Douglas, Suite One

Well Total Depth 4206 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 305

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: Day: 13 Month: 5 Year: 19 87

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 4198' PBD 4170' Perfs at 4140-58' Elevation 2139'KB Squeezed at 2990' w/50 sx

1st plug sand back to 4090' and dump 5 sx cement on top of sand through bailer,

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:30 p. Day: 29 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4090' and dumped 5 sx cement on top of sand

through bailer,

2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

released 8 5/8" wiper plug and pumped 150 sx cement.

RECEIVED

STATE CORPORATION COMMISSION

6-19-87
JUN 19 1987

Maximum pressure 800 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2314' of 5 1/2" casing

(If additional description is necessary, use BACK of this form.)

INVOICED
Please observe this plugging.

DATE 6-22-87

Signed Dan Goodrow (TECHNICIAN)

WV. NO. 17278