

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19044-00-00
Spot: SWNENW Sec/Twnshp/Rge: 29-26S-5E
990 feet from N Section Line, 1650 feet from W Section Line
Lease/Unit Name: KOUGLER Well Number: 104
County: BUTLER Total Vertical Depth: 2631 feet

Operator License No.: 32166
Op Name: DUNNE EQUITIES OPERATING, INC.
Address: 8100 E. 22ND ST. NO #1100
WICHITA, KS 67226

Conductor Pipe: Size feet: \$ 85.51
Surface Casing: Size 8.625 feet: 102 70 SX CMT
Production: Size 5.5 feet: 2627 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/15/2002 12:00 AM
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.
Proposal Rcvd. from: RICK MADDUX Company: DUNNE EQUITIES Phone: (316) 651-6023

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DONALD HOBERECHT Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 05/15/2002 12:00 AM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sand back to 2570' w/5sxs cement on top of sand. Perf casing at 250' could not pump in at 500lbs. Located cement at 104' b/w 5 1/2" and 8 5/8". Perf 5 1/2" at 103' and circulated cement to surface w/40sxs, 60/40 poz w/4% gel.

RECEIVED
KCC DISTRICT #2

MAY 16 2002

WICHITA, KS

Remarks: UNITED # 3970

Plugged through: CSG

District: 02

Signed 

(TECHNICIAN)

INVOICED

DATE

5-17-02

INV. NO.

2002061785

Form CP-2/3