

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19079-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 20-26S-5E
990 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: KOUGLER A Well Number: 109
County: BUTLER Total Vertical Depth: 2617 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size _____ feet:
Surface Casing: Size 10.75 feet: 79 80 SX CMT
Production: Size 7 feet: 2552 60 SX CMT
Liner: Size _____ feet:

\$85.05

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/29/2001 12:00 AM
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORP. Phone: (316) 682-1537

Proposed
Plugging
Method:

See actual report.

Plugging Proposal Received By: DONALD HOBERECHT Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 08/29/2001 12:00 AM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Spot 50sxs cement on bottom filled to 2314'(303' above open hole). Spot 40sxs at 274" thru 2" tub pull tub put swage on 7" and pumped 187sxs cement. Shut in. Run line top cement 124". Run 3/4" tub b/w 7" and 10 3/4" to 79'. Pumped 65sxs circulate to surface. Run 2" tub inside 7" to 124' and filled w/28sxs cement pull tub finished filling 7" w/15sxs cement.

RECEIVED
KCC DISTRICT #2

SEP 13 2001

WICHITA, KS

Remarks: UNITED CEMENT # 2276, 2277, 3434

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

INVOICE

DATE 9-19-01

NO. 2002060497

14