

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21069-00-00
Spot: SENENW Sec/Twnshp/Rge: 33-25S-5E
1305 feet from N Section Line, 2130 feet from W Section Line
Lease/Unit Name: PIERPOINT A Well Number: 113
County: BUTLER Total Vertical Depth: 2150 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 257 175 sx cmt \$ 69.88
Production: Size 5.5 feet: 2149 175 sx cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/18/2001 12:00 PM
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORP. Phone: (316) 682-1537

Proposed Plugging Method: SPOT 50 SX CLASS A PLUG OVER OPEN KC PERFS, TOP PERF 1945, WIRELINE TAG IT PERFS @ 307'. ESTABLISH CIRCULATION, MIX AND PUMP 60/40 POZMIX, 4% GEL, TO FILL CASING AND CIRCULATE UP BETWEEN 4-1/2" AND 8-5/8". CEMENT AND CAP WELL OFF.

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 05/18/2001 3:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Spot 50sxs cement at 1945' filled to 1584'. Perf casing at 307'. Circulated cement from 307'-0' w/ 135sxs 60/40 poz 4% gel.

RECEIVED
KCC DISTRICT #2

OCT 01 2001


WICHITA, KS

Remarks: UNITED # 3226

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 10-02-01

IV. NO. 2002060701

LR