

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19086-00-00  
Spot: SWSESW Sec/Twnshp/Rge: 5-25S-5E  
330 feet from S Section Line, 3630 feet from E Section Line  
Lease/Unit Name: DUNKLE Well Number: 9  
County: BUTLER Total Vertical Depth: 2497 feet

Operator License No.: 6804  
Op Name: LACHENMAYR OIL CO.  
Address: 904 EMMALINE  
NEWTON, KS 67114

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 0  
Production: Size 4.5 feet: 0  
Liner: Size feet:  
381.15

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/31/2001 12:00 AM  
Plug Co. License No.: 32147 Plug Co. Name: K.E. SNYDER CO., LLC  
Proposal Rcvd. from: HOWARD LACHENMAYR Company: LACHENMAYR Phone: (316) 283-2660

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DONALD HOBERECHT Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/31/2001 12:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sand back to 2400' w/4sxs cement on top of sand. No casing recovered. Cement from T.D. to surface. Set bridge in 4 1/2" at 270' cement to surface w/40sxs 60/40 poz. 4% gel. Cut window in 8 5/8" and run 1" tubing to 210' and pumped 200sxs 60/40 poz 4% gel from 210' -0' cement fell in 4 1/2" 84' filled w/25sxs. Ran 84' of 1" in 6 5/8" water well filled w/25sxs 60/40 poz 4% gel.

RECEIVED  
KCC DISTRICT #2

NOV 08 2001

WICHITA, KS

Remarks: UNITED # 3442

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

INVOICED  
DATE 11-9-01  
INV. NO. 2002060924

Form CP-2/3