

1 080581

Plugged 12-15-86

API NUMBER 15- 185-22,397-0000

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE SE SW, SEC. 20, T 23 S, R 11 W/E

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Geiding Hagen Well # 1-20

Operator: Murfin Drilling Company

County Stafford 125.13

Name & Address 250 North Water, Suite 300

Well Total Depth 3850 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 361

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Woodman-Iannitti Drilling Company License Number 6122

Address 805 Union Center Building, Wichita, KS 67202

Company to plug at: Hour: 12:30 p.m. Day: 15 Month: 12 Year: 19 86

Plugging proposal received from Rick Wheeler

(company name) Woodman-Iannitti Drilling Company (phone) 316-792-2921

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3700' with 50 sx cement, 2nd plug at 600' with 40 sx cement,

3rd plug at 390' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 p.m. Day: 15 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 3700' with 50 sx cement,

2nd plug at 600' with 40 sx cement,

3rd plug at 390' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
12-18-86  
DEC 18 1986

Remarks: Used 60/40 Pozmix 6% gel by Allied.

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE 12-31-86

Signed J. A. [Signature] (TECHNICIAN)

INV. NO. 15704 FEB 10 1987