

1041004

9-28

API NUMBER 15-007-21,220-0000

To: STATE CORPORATION COMMISSION

Wichita State Office Bldg. PLUGGING SECTION 150' S of NE SW SEC. 14, T 32 S, R 15 W/E

130 S. Market, Room 2078
Wichita, KS 67202

1830 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8653

Lease Name Swayden Well # 1

Operator: Petroleum Technologies, Inc.

County Barber 170.24

Name & Address: 500 Nichols Rd., Ste. 407

Well Total Depth 5238 feet

Kansas City, MO 64112

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 343

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Medicine Lodge, KS 67104

Company to plug at: Hour: 4:30 p.m. Day: 28 Month: 9 Year: 1995

Plugging proposal received from Alan Vratil

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 5200' w/150 sx cement, PBD 4760', Perfs at 4716-26'

1st plug sand back to 4675' and dump 5 sx cement on top of sand through bailer.

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5 p.m. Day: 28 Month: 9 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4666' and dumped 5 sx cement on top of sand bridge through bailer.

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3200' of 5 1/2" casing.

(If additional description is necessary, use BACK of Wichita, Kansas

observe this plugging.

INVOICED

DATE 10-9-95

INV. NO. 43706

Signed [Signature] (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION OCT 5 1995

CONSERVATION DIVISION