

1 020178

9-24

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,205-0000
90' W of
C N/2 N/2, SEC. 14, T. 32 S, R. 15 W/E

4620 feet from S section line
2730 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6167

Lease Name Alexander Well # 1

Operator: Hesse Petroleum Co./Hessco Inc.

County Barber 16341

Name & Address 400 North Woodlawn, Suite 7

Well Total Depth 5028 feet

Wichita, KS 67208

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 227

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Company License Number 5929

Address 205 East Central, Suite 120, Wichita, KS 67202

Company to plug at: Hour: 11 p.m. Day: 23 Month: 9 Year: 19 88

Plugging proposal received from John Armbruster

(company name) Duke Drilling Company (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2019'

1st plug at 1000' with 50 sx cement, 2nd plug at 260' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
9-27-88
SEP 27 1988
CONSERVATION DIVISION
KANSAS

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:30 a.m. Day: 24 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1000' with 50 sx cement,

2nd plug at 260' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

INVOICED
I (did not) observe this plugging.

DATE 10-4-88

Signed Glenn Barlow (TECHNICIAN)

WV. NO. 22445

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date September 14 1988 month day year

API Number 15-007-22,205-0000

OPERATOR: License # 6167 Name Hesse Petroleum Co./ Hessco Inc. Address 400 N Woodlawn, Ste 7 City/State/Zip Wichita, KS 67208 Contact Person Dave Hesse Phone 316-685-4746

90' W-C-N/2-N/2 Sec. 14 Twp. 32 S, Rg. 15 East West X West 4620' Ft. from South Line of Section 2730' Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5929 Name Duke Drilling Company City/State Wichita, KS

Nearest lease or unit boundary line 2550' feet County Barber

Lease Name Alexander Well # 1 Ground surface elevation 2019' feet MSL

Well Drilled For: X Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl X Wildcat Cable

Domestic well within 330 feet yes X no Municipal well within one mile: yes X no

Depth to bottom of fresh water 180' Depth to bottom of usable water 200'

Surface pipe by Alternate 1 X 2 Surface pipe planned to be set 225'

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

Conductor pipe required Projected Total Depth 5100' feet Formation Simpson

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 9-9-88 Signature of Operator or Agent Title Partner

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 225 feet per Alt. 1 X This Authorization Expires 3-12-89 Approved By LKM 9-12-88

EFFECTIVE DATE: 9-17-88

Moved in 9-15-88 + set 225' @ 8 1/2

90' W-C-N/2-N/2 Sec. 14 Twp. 32 S, Rg. 15 East West X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ Base Anh feet depth with 50 sxs of 60/40 Pos-Mix 2nd plug @ Base Surface feet depth with 40 sxs of 60/40 Pos-Mix 3rd plug @ 40' feet depth with 10 sxs of 60/40 Pos-Mix 4th plug @ feet depth with sxs of 5th plug @ feet depth with sxs of (2) Rathole with 1 sxs (b) Mousehole with sxs

PUSHER John Ambruster TD 5028 FORMATION Simpson SURFACE PIPE 8 1/2 @ 227 ANHYDRITE ? ELEVATION 2019 STARTING TIME & DATE 10:00 pm 9-24-88 COMPLETION TIME & DATE 12:30 pm 9-24-88 1st PLUG @ 1000 FT. W/ 50 SX 2nd PLUG @ 260 FT. W/ 40 SX 3rd PLUG @ 40 FT. W/ 10 SX 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ ✓ SX WATER WELL PLUGGED W/ ✓ SX CEMENT COMPANY BT Titan TECHNICIAN CB

RECEIVED 60-40 690 gals SEP 27 1988 CONSERVATION DIVISION Wichita, Kansas