

1 050160

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,552-0000
SE 1/4, SEC. 14, T 32 S, R 15W

660 feet from ~~N~~/S section line
660 feet from ~~W~~E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8653

Lease Name Larkin Well # 14-1

Operator: Petroleum Technologies, Inc.
Name & Address
4005 East Kellogg
Wichita, KS 67202

County Barber
Well Total Depth 5226 169.84 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 403

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address 107 West Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 8:00 am Day: 1 Month: March Year: 19 84

Plugging proposal received from Elmo Morgenstern

(company name) X Clarke Corporation (phone) 316-886-5665

were: 5 1/2 set at 5111' Perfs 3923 CIBP at 4930'

1st plug sand back to 3875' with 5 sx cement dumped on top of sand

2nd plug pump through head with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and release 8 5/8" rubber plug and pump an additional 100 sx cement.

Maximum pressure 500# and shut-in pressure 300#

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:00 noon Day: 1 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 5111' Perfs 3923' CIBP at 4930'

1st plug sanded back to 3875' with 5 sx cement dumped on top of sand

2nd plug pumped through head with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and released 8 5/8" rubber plug and pumped an additional 100 sx cement.

Maximum pressure 500# and shut-in pressure 300#

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun. They recovered 2800' of 5 1/2" casing (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-12-84

INV. NO. 0682

RECEIVED

STATE CORPORATION COMMISSION Signed

MAR 07 1984

3-7-84 CONSERVATION DIVISION

Richard W. Lacey (TECHNICIAN)