

1080121 (TMB. KCC)
20301-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007 -20,279

C-W/2 NW, Sec. 1, T 33 S, R 13 W/E
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5023

Lease Name Lonker Well # M-1

Operator: Kansas Petroleum, Inc.
Name & 225 North Market, Suite 310
Address Wichita, KS 67202

County Barber

Well Total Depth 3893 feet 126.53

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 314

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 am Day: 21 Month: March Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Norman Voth

(company name) Kelso (phone) 316-938-2457

were: 4 1/2 set at 3893 PBDT 3867 Perfs 3814 - 16

Pumped 25 sx cement on bottom Maximum pressure 2000# Shut-in pressure 1600

Squeezed well with 2 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 2 sx hulls

and 120 sx cement. Maximum pressure 400# Shut-in pressure 300#

Signed *J. H. Meij*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00 am Day: 21 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 3898 PBDT 3867 Perfs 3814 - 16

Pumped 25 sx cement on bottom - maximum pressure 2000# and shut-in pressure 1600#

Squeezed well with 2 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 2 sx hulls and

120 sx cement. - Maximum pressure 400# and shut-in pressure 300#

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied. They recovered 3190' of 4 1/2" production casing.

RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1984
3-29-84
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as hereinafter stated and that I (did / ~~did not~~) observe this plugging.

Signed *J. H. Meij*
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 3-29-84

INV. NO. 0988