

5-20

2-040882

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-077-21,310-00-00

W/2 E/2 NE, SECTION 15 TOWNSHIP 33 RANGE 6W

OPERATOR LICENSE # 8061 3960 FEET FROM S SECTION LINE
OPERATOR OIL PRODUCERS INC OF KANSAS 660 FEET FROM E SECTION LINE
NAME & P.O. BOX 8647
ADDRESS WICHITA, KS 67208

LEASE NAME: HARRISON #1
COUNTY: HARPER 149.47
WELL TOTAL DEPTH: 4599' PBD 4425'
PIPE: 4 1/2" @ 4598'
SURFACE CASING: 8 5/8" @ 229'

(L)

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: D S & W WELL SERVICING INC

ADDRESS: CLAFLIN, KS LICENSE: 6901

COMPANY TO PLUG AT: HOUR: DAY: MONTH: YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: KENT STRUBE

COMPANY NAME: D S & W WELL SERVICING INC PHONE: (316) 587-3361

WERE: SAND TO 4363' AND 4 SACKS OF CEMENT
35 SACKS AT 950'
35 SACKS AT 625'
CIRCULATE 280' TO SURFACE

PLUGGING PROPOSAL RECEIVED BY: SVG

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { X } NONE { }

COMPLETED: HOUR: 14:30 DAY: 20 MONTH: 5 YEAR: 1997

ACTUAL PLUGGING REPORT: THE PERFS WERE COVERED WITH SAND FROM 4425' TO 4350' AND CAPPED WITH 4 SACKS OF CEMENT. 4 1/2" RECOVERED FROM 3545' AND PULLED TO 972' WHERE 35 SACKS OF CEMENT WAS SPOTTED. 4 1/2" PULLED TO 620' WHERE 35 SACKS OF CEMENT WAS SPOTTED. 4 1/2" PULLED TO 294' WHERE CEMENT WAS CIRCULATED TO SURFACE. REMAINING PIPE PULLED AND CEMENT WAS TOPPED OFF.

REMARKS: 60/40 POZ 4% GEL ALLIED CEMENTING

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 05 1997

I DID OBSERVE THIS PLUGGING.

Steve Van Gieson

STEVE VAN GIESON

CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE JUN 09 1997

INV. NO. 48297

FORM CP-2/3

REV. 3/90