

1050868

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,091 ~~000~~

W/2 NW NW, SEC. 26, T 18 S, R 21 W/E

4620 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Shank Well # 1

Operator: Berexco Inc.
Name & Address: 970 Fourth Financial Center
Wichita, KS 67202

County Ness 136.50

Well Total Depth 4200 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Beredco Inc. License Number 5147

Address 401 E. Douglas, #402, Wichita, KS 67202

Company to plug at: Hour: 5 a.m. Day: 5 Month: 1 Year: 19 87

Plugging proposal received from Howard Cain

(company name) Beredco Inc. (phone) 316-653-2463

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2098' Anhydrite 1322-52'

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at Base Cheyenne with

100 sx cement, 3rd plug at Dakota with 50 sx cement, 4th plug at 30' below base

of surface pipe with 10 sx cement, 5th plug at 40-0' with 10 sx cement, 6th plug

to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7 a.m. Day: 5 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1350' with 50 sx cement,

2nd plug at 720' with 100 sx cement,

3rd plug at 330' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 2% cc by B.J. Titan.

STATE CORPORATION COMMISSION
1-6-87
JAN 6 1987
CONSERVATION DIVISION
Wichita, Kansas

INVOICED (Additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 1-7-87

Signed Richard W. Lacey (TECHNICIAN)

WV. NO. 15816

1-5

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 12/29/86 month day year

API Number 15-135-23,091-0000

OPERATOR: License # 5363 Name BEREXCO, INC. Address 970. Fourth Financial Center City/State/Zip Wichita, Kansas 67202 Contact Person J. D. Marcus Phone (316) 265-3311

W/2 NW NW Sec. 26 Twp. 18 S, Rg. 21 X West 4620 Ft. from South Line of Section 4950 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5147 Name BEREDCO, INC. City/State Wichita, Kansas

Nearest lease or unit boundary line 330 feet County Ness Lease Name Shank Well # 1 Ground surface elevation 2098 feet MSL

Well Drilled For: X Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water 100 Depth to bottom of usable water 1100 3000

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Surface pipe by Alternate: 1-2 X Surface pipe planned to be set 300 Conductor pipe required Projected Total Depth 4200 feet Formation Mississippian

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 11/13/86 Signature of Operator or Agent J. D. Marcus Title Executive Vice President

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X This Authorization Expires 6-23-87 Approved By 12-23-86

SPUD 12-29-86 300' 8 1/8"

Handwritten signature

W/2 NW NW Sec. 26 Twp. 18 S, Rg. 21 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

- 1st plug @ Base Anhydrite feet depth with 50 sxs of .60/40 Pozmix, .6% Gel, .3% CC
2nd plug @ Base Cheyenna feet depth with 100 sxs of .60/40 Pozmix, .6% Gel, .3% CC
3rd plug @ Dakota feet depth with 50 sxs of .60/40 Pozmix, .6% Gel, .3% CC
4th plug @ 30' below base surf feet depth with 10 sxs of .60/40 Pozmix, .6% Gel, .3% CC
5th plug @ 40'-0' feet depth with sxs of
(2) Rathole with 15 sxs (b) Mousehole with 10 sxs

Table with columns: PUSHER, TD, SURFACE PIPE, ANHYDRITE, STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @, 2nd PLUG @, 3rd PLUG @, 4th PLUG @, RAT HOLE CIRCULATED, MOUSE HOLE CIRCULATED, WATER WELL PLUGGED, CEMENT COMPANY, TECHNICIAN. Includes handwritten entries like 'Howard Lewis', 'FORMATION MISSI', '8 7/8 @ 302', '1322 ELEVATION 2098', '5:00 am 1/5/86', '7:00 am 1/5/86', 'BT Hughes', 'STEVE', '60/40 poz 6% gel 2% cc'.

STATE CORPORATION COMMISSION JAN 6 1987 CONSERVATION DIVISION Wichita, Kansas