

To: 1 070004

API NUMBER 15-7-25-58 135-00557-0000 R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE NE SW, SEC. 24, T 18 S, R 21 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5088

Lease Name Pabst Well # A-1

Operator: John Jay Darrah, Jr.
Name & Address: 405 Century Plaza
Wichita, KS 67202

County Ness 135.53
Well Total Depth 4170 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8" feet 557

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor John Jay Darrah, Jr. License Number 5088

Address 405 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 10:45 am Day: 2 Month: July Year: 19 85

Plugging proposal received from Flip Phillips

(company name) John Jay Darrah, Jr. (phone) 316-263-2243

were: 5 1/2" at 4167' Perfs at 4049-4055' Stage collar at 1301 with 200 sx to surface
Squeeze well with 1 sack hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:30 am Day: 2 Month: July Year: 19 85

ACTUAL PLUGGING REPORT Squeezed well with 1 sack hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION

7-9-85

Maximum pressure 1000 psi and shut in 450 psi

Remarks: Used 60/40 Pozmix 6% gel by Dowell. No recovery. Wichita, Kansas

(if additional description is necessary, use BACK of this form.)

INVOICED (if desired, observe this plugging.)

DATE 7-17-85

Signed Dan Godrow (TECHNICIAN)

INV. NO. 8997

7-2 AUG 06 1985