

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

4 (all)

API Well Number: 15-077-21477-00-00  
Spot: W2NW Sec/Twnshp/Rge: 28-33S-6W  
3860 feet from S Section Line, 4620 feet from E Section Line  
Lease/Unit Name: WITTERS Well Number: 1  
County: HARPER Total Vertical Depth: 4918 feet

Operator License No.: 6236  
Op Name: M.T.M. PETROLEUM  
Address: PO BOX 82  
SPIVEY, KS 67142

Conductor Pipe: Size feet: 159.84  
Surface Casing: Size 8.625 feet: 260  
Production: Size feet:  
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 12/31/2002 2:00 AM

Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.

Proposal Rcvd. from: JOHN ARMBRUSTER Company: DUKE DRILLING Phone: (316) 267-1331

Proposed Plugging Method: 35sks@ 1050', 35 sks @ 700', 35 sks @ 310', 25 sks @ 60', 15 sks@ RH, 15 sks @ MH

RECEIVED  
KCC DISTRICT #2  
JAN 8 2003

WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 12/31/2002 2:00 AM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:


The Drill pipe was run open end to 1050', where 35 sks of cement was spotted. The drill pipe was pulled to 700', where 35 sks of cement was spotted. The drill pipe was pulled to 310', where 35 sks of cement was spotted. The drill pipe was pulled to 60', where cement was circulated to surface. The Rathole was circulated with 15 sks of cement. The Mousehole was circulated with 15 sks of cement.

Remarks: ALLIED CEMENTING 60/40 POZ 4% GEL

Plugged through: DP

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE 1-28-03

TR. NO. 2003061122