

1 060558

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION NE SE NW  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,779 -00-00

3600 feet from S section line  
3100 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Larson "A" Well # 3

Operator: TXO Production Corp.  
Name & Address: 200 W. Douglas, Suite 300  
Wichita, KS 67202

County Barber 147.07

Well Total Depth 4525 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Oilfield Services License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 2:00 pm Day: 9 Month: May Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 4517' PBTD 4156' Perfs at 4441-46'; 4418-22'; 4024-28'

1st plug sand back to 3975' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:00 pm Day: 9 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3975' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAY 13 1985

CONSERVATION DIVISION Wichita, Kansas

Maximum pressure 750 psi and shut in 600 psi

Remarks: Recovered 3250' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by B J-Titan (if additional description is necessary, use BACK of this form.)

(did ~~not~~) observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

VOICED  
DATE 5-14-85  
INV. NO. 8143