

To: 1 040705 10-9
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
250 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-22,142-00-00 88P
150' N of
SW NE NE, SEC. 12, T 32 S, R 13 W/EX
4440 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5020
Operator: Rine Drilling & Exploration, Inc.
Name &
Address 200 W. Douglas, Ste. 1050
Wichita, KS 67202-3010

Lease Name Vanderwork "B" Well # 1-12
County Barber 143.20
Well Total Depth 4406 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 355

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
never produced
Other well as hereinafter indicated _____

Plugging Contractor Clarke Well Service License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10 a.m. Day: 9 Month: 10 Year: 19 92

Plugging proposal received from Jeff Clarke
(company name) Clarke Well Service (phone) 316-886-5665

were: 4 1/2" at 4406' w/225 sx cement, PBSD 4331', Perfs at 4242-48, 4272-86'
1st plug sand back to 4190' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 9 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4190' and dumped 4 sx cement on top of
sand bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement. **RECEIVED**
Maximum pressure 800 psi and shut in 600 psi. STATE CORPORATION COMMISSION
OCT 16 1992

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3100' of 4 1/2" casing
(if additional description is necessary, use BACK of this form.)

INVOLVED
Did you observe this plugging.

DATE 10-29-92
INV. NO. 36641

Signed Stephen J. Pfeiffer
(TECHNICIAN)