

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-21967-00-00  
Spot: E2SESE Sec/Twnshp/Rge: 15-32S-13W  
660 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: BROOKS-YOUNGER Well Number: 6  
County: BARBER Total Vertical Depth: 4620 feet

Operator License No.: 31980  
Op Name: LOTUS OPERATING COMPANY, L.L.C.  
Address: 914 E DOUGLAS  
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 4618  
Surface Casing Size: 8.625 feet: 278  
*B 150' 15*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/17/2003 2:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK TO 4030' WITH 5 SX CMT ON TOP. PLUG AT 600' WITH 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 07/17/2003 3:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4606'. PERFS AT 4080-90, 4266-67, 4526-38'. SANDED BACK TO 4000' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED  
JUL 25 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2810' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
JUL 21 2003  
KCC Dodge City

Signed Stephen J. Pfeifer  
(TECHNICIAN)

INVOICED  
DATE 7-25-03  
2004060156

*[Handwritten signature]*  
Form CP-2/3