

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21968-00-00
Spot: NESWSENE Sec/Twnshp/Rge: 15-32S-13W
2210 feet from N Section Line, 750 feet from E Section Line
Lease/Unit Name: BROOKS-YOUNGER Well Number: 5
County: BARBER Total Vertical Depth: 5030 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 914 E DOUGLAS
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 4691
Surface Casing Size: 8.625 feet: 297

163 48

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/17/2003 11:45 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 07/17/2003 12:30 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: STEVE PFEIFER

Actual Plugging Report:


PBTD 4666'. PERFS AT 4541-51 & 4552-68'. SANDED BACK TO 4490' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. PUMPED DOWN 8 5/8" SURFACE PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 800#. SHUT IN PRESSURE 400#.

RECEIVED
JUL 25 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2747' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 7-25-03

NO. 2004060156

Form CP 23