

To: 1 052063
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 8/1/66 15-007-30245-0000
C SE SE, SEC. 30, T 32 S, R 11 W XX
660 feet from S section line
660 feet from E section line

8-19
TECHNICIAN'S PLUGGING REPORT
Operator License / 3308
Operator: Casey Musgrove Oil
Name: _____
Address Rt. 2, Box 401
Ponca City, OK 74604

Lease Name McClure Well # 2
County Barber 121.68
Well Total Depth 3744 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 1 p.m. Day: 19 Month: 8 Year: 19 96

Plugging proposal received from Alan Vratil
(company name) Clarke Corporation (phone) 316-886-5665

Notes: 4 1/2" at 3744', Perfs at 3555-67'
1st plug sand back to 3500' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 1:30 p.m. Day: 19 Month: 8 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3500' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 550 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1996
8-22-96

INVOICED
DATE AUG 28 1996
WVZ MEL 43676

Signed Richard W. Lacey (TECHNICIAN)