

To: 1 041190
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Drilled 5/66 15-007-30244-0000
C SW SE, SEC. 30, T 32 S, R 11 W/E
660 feet from S section line
1980 feet from E section line

7-25
TECHNICIAN'S PLUGGING REPORT
Operator License / 3308
Operator: Casey Musgrove Oil
Name:
Address Rt. 2, Box 401
Ponca City, OK 74604

Lease Name McClure Well # 1
County Barber 120.99
Well Total Depth 3723 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well Gas Well Input Well SMD Well D&A
Other well as hereinafter indicated
Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS
Company to plug at: Hour: 9:15 a.m. Day: 25 Month: 7 Year: 96

RECEIVED
KANSAS CORP. COMM
316-8886-5665
31835
AUG 10 12 09
7-30-96

Plugging proposal received from Alan Vratil
(company name) Clarke Corporation (phone) 316-8886-5665

Work: 4 1/2" at 3723' w/125 sx cement, Perfs at 3550-60', Casing leak at 1288'
1st plug sand back to 3500' and dump 4. sx cement on top of sand through bailer,
2nd plug run tubing to 600', fill with gel, and spot 50 sx cement.
3rd plug spot 30 sx cement at 240',
4th plug spot 10 sx cement at 40'.

Plugging Proposal Received by Kevin Strube
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 10 a.m. Day: 25 Month: 7 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 2950' and dumped 4 sx cement on top of sand
bridge through bailer, Ran tubing in to spot plugs; displaced hole with gel:
2nd plug at 590' with 50 sx cement,
3rd plug at 240' with 50 sx cement,
4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel, 3% cc by Allied. Recovered 1100' of 4 1/2" casing.
(if additional description is necessary, use BACX of this form.)

INVOICED
AUG 08 1995
Observe this plugging.
463.12

Signed Stephen J. DeFoe
(TECHNICIAN)