

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-30242-00-00⁰¹
Spot: W2SESW Sec/Twnshp/Rge: 30-32S-11W
660 feet from S Section Line, 1980 feet from W Section Line
Lease/Unit Name: GRIGSBY Well Number: 1
County: BARBER Total Vertical Depth: 3740 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

Conductor Pipe: Size feet: 121.55
Surface Casing: Size 8.625 feet: 204 WITH 200 SX CMT
Production: Size 4.5 feet: 3838 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/31/2002 1:20 PM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: AARON HAMMERSCHMID Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: SAND TO 3400' & 4 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 230' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/31/2002 2:15 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PBTD 3590'. PERFS AT 3540-50'. SAND BACK TO 3400' & 4 SX CMT. 1ST PLUG SPOT 10' SX GEL & 50 SX CMT AT 600'. 2ND PLUG SPOT 50 SX CMT AT 230'. 3RD PLUG SPOT 20 SX CMT AT 0-40'. GOOD CIRCULATION.

RECEIVED
AUG 09 2002
8-9-02
KCC WICHITA

Remarks: USED 60/40 POZMIX 6& GEL BY ALLIED. RECOVERED 988' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed [Signature]
(TECHNICIAN)

INVOICED
DATE 8-9-02
AUG 01 2002
WELL NO. 2003060204
AP

Folio 2/3
[Signature]