

259
R

To: 1010092
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,690-~~0000~~
C W/2 SW, SEC. 29, T 32 S, R 11 W
1320 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5105
Operator: Clarke Corporation
Name & Address: P. O. Box 187
Medicine Lodge, KS 67104

Lease Name Zimmerman Well # 4
County Barber 120.25
Well Total Depth 3700 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 212

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:20 am Day: 18 Month: February Year: 19 86

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 3692' PBD 3650' Perfs at 3594-3606'

1st plug sand back to 3540' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 am Day: 18 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3540' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

Maximum pressure 550 psi and shut in 350 psi

Remarks: Recovered 3000' 4 1/2" casing. Used 60/40 Pozmix 2% cc by BJ-Titan (if additional description is necessary, use BACK of this form.)

INVOICED
DATE FEB 26 1986
INV. NO. 12680

observe this plug-log
STATE CORPORATION COMMISSION

FEB 24 1986
2-24-86
CONSERVATION DIVISION
Wichita, Kansas

Signed *Jack R. Smith*
(TECHNICIAN)