

11-2

2-040579

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-077-20,777- D-22,153

S/2 S/2 NW, SECTION 8 TOWNSHIP 32 RANGE 9W

OPERATOR LICENSE # 5042 FEET FROM S SECTION LINE \_\_\_\_\_  
FEET FROM E SECTION LINE \_\_\_\_\_

OPERATOR Edmiston Oil Company  
NAME & 125 N. Market, #1260  
ADDRESS Wichita, KS 67202

LEASE NAME: Easterby #1  
COUNTY: Harper  
WELL TOTAL DEPTH: 4379' 142.31

CONDUCTOR PIPE: " @ ' "  
SURFACE CASING: 8-5/8" @ 285'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD X D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Company Tools  
ADDRESS: \_\_\_\_\_ LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Dale Maus  
COMPANY NAME: Edmiston PHONE: \_\_\_\_\_

WERE: Sand to 3500' & 4 sx - sand to 4278' & 4 sx - 20 sx @  
2870' - 35 sx @ 2250' - 35 sx @ 1450' - 35 sx @ 900' -  
circ 340' - 4-1/2" 4379' - Miss perf 4328-34' - KC disp  
perfs.

PLUGGING PROPOSAL RECEIVED BY: Don Thompson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART ( X ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 1630 DAY: 2 MONTH: 11 YEAR: 1990

ACTUAL PLUGGING REPORT:  
Production perfs were sanded back to 4278' & 4 sx cmt  
- KC disposal perfs sanded back from 4278' to 3500' &  
again capped w/4 sx cmt - 4-1/2" was recovered from  
2870' where 20 sx cmt spotted - 35 sx cmt each was also  
spotted thru csq at 2250', 1450', 900' - cmt was circ  
to surface at 340'

REMARKS: B.J. Services #611047 common cement

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 11-19-90

INV. NO. 30011  
11-2

Steve Van Gieson  
Steve Van Gieson (AGENT)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 09 1990  
11-9-90  
CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
REV. 3/90

15-077-70777-0000

# Electra Log Inc.

Sec. 8 Twp. 32s Rge. 9w

## Radiation Guard Log

MAY 25 1982

COMPANY RAM PETROLEUM CORPORATION

WELL EASTERBY #1

FIELD SHARON

COUNTY HARPER

STATE KANSAS

Location

C S/2 S/2 NW/4

Other Services:

Sec. 8

Twp. 32s Rge. 9w

Permanent Datum: GROUND LEVEL Elev. 1469'

Log Measured From: K.B. EIGHT Ft. Above Perm. Datum

Drilling Measured From: KELLY BUSHING

Elev. K.B. 1477'

D.E. 1474'

G.L. 1469'

Date 4-2-80

Run No. ONE

Depth - Driller 4380'

Depth - Logger 4370'

Btm. Log Inter. 4369'

Top Log Inter. 0

Casing - Driller 8 5/8 @ 327'

Casing - Logger

Bit Size 7 7/8

Type Fluid in Hole STARCH

Dens. 8.5 Visc. 44

pH 9 Fluid Loss 19.2 ml

Source of Sample FLOLINE

Rm. @ Meas. Temp. .42 @ 63 F

Rm. @ Meas. Temp. .31 @ 63 F

Rm. @ Meas. Temp. .63 @ 63 F

Source: Rm. Rm. CHARTS

Rm. @ BHT .22 @ 119 F

Time Since Circ. 3 hours

Max. Rec. Temp. 119 F

Equip. Location 140 GREAT BEND

Recorded By C. BAKER

Witnessed By MR. PERRY HAND

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 25 1990  
10-25-90  
CONSERVATION DIVISION  
Wichita, Kansas