

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

3-27

API NUMBER: 15-07721296-0000
C-NE-NW, SECTION 7 TOWNSHIP 32 RANGE 9 W

OPERATOR LICENSE # 31532 4620 FEET FROM S SECTION LINE
3300 FEET FROM E SECTION LINE

OPERATOR BISON PRODUCTION COMPANY
NAME & 9320 EAST CENTRAL
ADDRESS WICHITA, KS 67212

LEASE NAME: GREIVING 1-7
COUNTY: HARPER
WELL TOTAL DEPTH: 4470' 145.27
CONDUCTOR PIPE: _____
SURFACE CASING: 8 5/8" @ 224'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____
PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE
ADDRESS: ATTICA, KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: RUSSEL MEYERS
COMPANY NAME: BISON PRODUCTION COMPANY PHONE: 316-
WERE: 5 1/2 4459' SAND TO 4419' AND 5 SACKS CEMENT
RECEIVED 5 1/2
35 SACKS 1600'
35 SACKS 905'
CIRC. CEMENT 274'

PLUGGING PROPOSAL RECEIVED BY: _____
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { _____ } NONE { _____ }

COMPLETED: HOUR: 16:30 DAY: 27 MONTH: 3 YEAR: 1996

ACTUAL PLUGGING REPORT:

THE PERFS WERE COVERED WITH SAND FROM 4470' TO 4419' AND CAPPED WITH 5 SACKS OF CEMENT. THE 5 1/2 WAS RECOVERED FROM 3375' AND PULLED TO 1638' WHERE 35 SACKS OF CEMENT WAS SPOTTED. PULL PIPE TO 905' WHERE 35 SACKS OF CEMENT WAS SPOTTED. THE PIPE WAS PULLED TO 274' WHERE CEMENT WAS CIRCULATED TO SURFACE. REMAINING PIPE PULLED AND CEMENT TOPPED OFF.

REMARKS: ALLIED CEMENT 60/40 4%

I DID NOT OBSERVE THIS PLUGGING.

Steve V. Gieson
(AGENT) Steve Van Gieson

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 27 1996
6-27-96
CONSERVATION DIVISION
WICHITA, KS

FORM CP-2/3
REV. 3/90

INVOICED
DATE JUN 28 1996
INV. NO. 44902