

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21443-00-00
Spot: NESW Sec/Twnshp/Rge: 7-32S-9W
1980 feet from S Section Line, 1980 feet from W Section Line
Lease/Unit Name: STONE Well Number: B-3
County: HARPER Total Vertical Depth: 4460 feet

Operator License No.: 5429 Conductor Pipe: Size feet: 8144.95
Op Name: HAYES, BRYCE F., DBA BRYCE F. OIL & Surface Casing: Size 8.625 feet: 225
Address: 1081 WEST HIGHWAY 160 PO BOX 108 Production: Size feet:
ATTICA, KS 67009 Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 12/02/2002 1:30 AM

Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.

Proposal Rcvd. from: MIKE GODFREY Company: DUKE DRILLING Phone: (316) 267-1331

Proposed Plugging Method: 35 SKS @ 1500', 35 SKS @ 900', 35 SKS @ 275', 25 SKS @ 60', 15 SKS IN RH, 15 SKS MH

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 12/02/2002 1:30 AM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:


THE DRILL PIPE WAS RUN OPEN ENDED TO 1500', NWHERE 35 SKS OF CEMENT WAS SPOTTED IN PLACE. THE DRILL PIPE WAS PULLED TO 900', WHERE 35 SKS OF CEMENT WAS SPOTTED IN PLACE. THE DRILL PIPE WAS PULLED TO 275', WHERE 35 SKS OF CEMENT WAS SPOTTED IN PLACE. THE DRILL PIPE WAS PULLED TO 60', WHERE 25 SKS OF CEMENT WAS CIRCULATED TO SURFACE. THE RAT HOLE WAS CIRCULATED WITH 15 SKS OF CEMENT. THE MOUSE WAS CIRCULATED WITH 15 SKS OF CEMENT.

Remarks: ALLIED CEMENTING 60/40 4% GEL

Plugged through: DP

District: 02

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 12-10-02

INV. NO. 2003060928