

8-30

2-040564

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

SEP - 7 1990
9-13-90

CONSERVATION DIVISION
Wichita, Kansas

API NUMBER: 15-677-20767-0000

SE SW NE , SECTION 7 TOWNSHIP 32 RANGE 9W

OPERATOR LICENSE # 6581 2970 FEET FROM S SECTION LINE
1650 FEET FROM E SECTION LINE

OPERATOR Bison Energy Corp.
NAME & P. O. Box 782317
ADDRESS Wichita, KS 67278

LEASE NAME: Heath #4

COUNTY: Harper
WELL TOTAL DEPTH: 4430' -143.97

PIPE: " @
SURFACE CASING: 8-5/8" @ 291'

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Great Bend Casing Pulling
ADDRESS: Great Bend, KS LICENSE: 4635

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Gary Burke
COMPANY NAME: Great Bend Casing PHONE: _____

WERE: 5-1/2" @ 4429' - perfs 4356-4362' - sand to 4300' & 5
sx - recover pipe - 35 sx 1400' - 35 sx @ 1000' - circ
340'.

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (X) NONE ()

COMPLETED: HOUR: 21:00 DAY: 30 MONTH: 8 YEAR: 1990

ACTUAL PLUGGING REPORT:
The perfs were closed by pumping 50 sx cmt to 4100' on
8/29/90 - 5-1/2" was recovered from 2720' & pulled to
1402' where 35 sx cmt spotted - 5-1/2" pulled to 1000'
& 35 sx cmt spotted - 5-1/2" again pulled to 320' &
circ to surface.

REMARKS: B.J. Services #611009 60/40 4%

I DID OBSERVE THIS PLUGGING.

Steve Van Gieson
Steve Van Gieson (AGENT)

INVOICED

FORM CP-2/3
REV. 3/90

DATE: SEP 17 1990

INV. NO. 29316

MK