

49
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

spot oil 7-7-69

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15135-19106 0000

Operator's Full Name Four Way Operating

Complete Address: Box 698 Great Bend, Kansas 67530

Lease Name Pabst "A" Well No. 2

Location SE NE NW Sec. 24 Twp. 18 Rge. (E) (W) 21

County Ness Total Depth 4158

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Csg. Plg.

Address: Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 10:45A Day 19 Month 7 Year 1969

The Above well was plugged as follows:

Total Depth 4158' 8 5/8 csg set at 1289' cwc 880 sk.

5 1/2 csg 4156' cw 100 sk cmt.

5 1/2 csg PBTD 4126 with top perf. (4070)

Filled 5 1/2 csg W/sd (4050-4126) dumped 5 sk cmt W/dump bailer (4010-4050)

Cutoff and recovered 3220' of 5 1/2 csg.

Mud to 435' set rock bridge (420-435) Filled to surface with 6 yds readymix cmt.

RECEIVED
STATE CORPORATION COMMISSION *7-24-69*

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/24/69
INV. NO. 147-11

CONSERVATION DIVISION
Wichita, Kansas
Leo J. Mearns
Well Plugging Supervisor