

15-135 00560 0000

183

KANSAS
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

DEC 27 1961
12-27-61
CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ness

Location: NW SE NW Sec. 24 Twp. 18 Rge. _____ (E) _____ (W) 21

Name of Field: _____ Total Depth: 4145

I have this date completed supervision of plugging of:

Lease Name: Pabst Well No. A-2

Operator's Full Name: R. W. Shields

Complete Address: 308 Rule Bldg Wichita, Kansas

Plugging Contractor Central Pipe Pulling

Address: Great Bend, Kansas License No. 459

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 21 Month 12 Year 61

The above well was plugged as follows:

8 5/8" 1318' circulated with cement - 5 1/2" 4144' with 100 sax cement.

PB to 4140' - perf 4062

Filled with sand to 400', set 4 sax cement with dump bailer - pulled

2587' 5 1/2" - mudded hole to 1275', set plug, 2 sax calseal and 20 sax cement,

heavy gel mud to 200', set plug, rock bridge and 25 sax cement, heavy gel

mud to 35', set rock and 10 sax cement to bottom cellar.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 1/22/62
INV. NO. 4234-W